

HIGHWAY FOREMAN JIM POTTER

SELECTBOARD JOHN PETERS JR, CHAIR **BENJAMIN BRICKNER, VICE-CHAIR STEVE CHAMBERLIN** MEG EMMONS EMILY GRUBE

TOWN OF POMFRET, VERMONT DECEMBER 2023

WILD APPLE ROAD IMPROVEMENTS

| Sheet | |
|-------|--|
| G-1.0 | |
| C-1.0 | |
| C-1.1 | |

| WILD APPLE ROAD SITE | Roadway D Town High Annual Ave AADT, Des Proposed S Local ID Nu Northing/E Structure T Design Live Clear Span <u>Hydraulic D</u> Waterbody Drainage A Design Flow Stone Arme |
|----------------------|--|
| | |

Sheet List Table

Sheet Title

TITLE PAGE WILD APPLE ROAD SITE PLAN

DETAILS

Design Information nway Number: 33 erage Daily Traffic (AADT), Current: Est. <400 sign Forecast (20 Year): Est. <400

Structure Design Information umber: #15 Easting: 43.6872 / -72.5616 Type: Precast Concrete Box ve Load: HL-93 า: 15'

Design Information y: Un-named Tributary to Barnard Brook Area: $\sim 1.62 \text{ mi}^2$ ow (Q25): 237 cfs nor Min. Size: VTrans Specification E2



GENERAL/CONSTRUCTION NOTES

- TO CLARIFY THE PLANS, ALL EXISTING SITE FEATURES ARE SHOWN IN IOwercase LETTERS AND ALL PROPOSED IMPROVEMENTS ARE SHOWN IN CAPITAL LETTERS.
- THIS PLAN SHOWS APPROXIMATE SITE FEATURES, UTILITIES, TAX MAP BOUNDARY LINES, BUILDINGS, AND OTHER SITE FEATURES BASED ON A SURVEY COMPLETED BY EAST ENGINEERING IN FEBRUARY 2023. ADDITIONAL DEPICTIONS ARE BASED ON INFORMATION FROM THE VERMONT
- GEODATA PORTAL, OWNER, AND UTILITY COMPANIES. THIS IS NOT A BOUNDARY SURVEY. TECHNICAL SPECIFICATIONS ACCOMPANY THE PLANS AND ARE ESSENTIAL FOR CONSTRUCTION. UNLESS OTHERWISE NOTED, THE VERMONT AGENCY OF TRANSPORTATION (VTRANS) 2018 STANDARD SPECIFICATIONS FOR CONSTRUCTION SHALL BE FOLLOWED. CONTRACTOR FIELD PERSONNEL SHALL HAVE THE PLANS, SPECIFICATIONS, AND BID DOCUMENTS IN THE FIELD DURING CONSTRUCTION.
- ALL SITE SAFETY, SECURITY, MEANS AND METHODS ARE THE RESPONSIBILITY OF THE CONTRACTOR. ALL OSHA/VOSHA RULES AND REGULATIONS SHALL BE ADHERED TO AT ALL TIMES. AT THE END OF EACH WORKING DAY, CONTRACTOR SHALL SECURE ALL EQUIPMENT, MATERIALS, AND FACILITIES. ALL OPEN EXCAVATIONS SHALL BE BARRICADED, FENCED, PLATED, COVERED OR TEMPORARILY BACKFILLED.
- ALL APPLICABLE PERMITTING CONDITIONS AND REGULATIONS SHALL BE MAINTAINED BY THE CONTRACTOR.
- NO WORK OUTSIDE OF THE TOWN RIGHT-OF-WAY, OR TOWN OBTAINED EASEMENTS, UNLESS WRITTEN PERMISSION FROM BOTH THE LANDOWNER AND ENGINEER ARE OBTAINED.
- TRAFFIC SHALL BE DETOURED DURING THE ROAD CLOSURE. MAXIMUM ROAD CLOSURE SHALL BE 21 DAYS - ONE LANE DURING WORKING HOURS, TWO LANES AFTER WORKING HOURS MUST BE RESTORED AT THE END OF 21 DAYS.
- ALL DISTURBED AREAS SHALL BE RESTORED TO PRE-CONSTRUCTION CONDITIONS OR BETTER. THE PROJECT IS NOT REQUIRED TO OBTAINED COVERAGE UNDER THE STATE OF VERMONT, AGENCY OF NATURAL RESOURCES, DEPARTMENT OF ENVIRONMENTAL CONSERVATION, CONSTRUCTION GENERAL PERMIT (3-9020) FOR STORMWATER GENERATED FROM THE PROJECT. HOWEVER, BEST MANAGEMENT PRACTICES FOR EROSION PREVENTION AND SEDIMENT CONTROL SHALL BE MAINTAINED REGARDLESS.
- DISTURBED AREAS NOT UNDER ACTIVE CONSTRUCTION SHALL BE STABILIZED WITHIN 7 DAYS. IF TURBID WATER IS FOUND TO BE LEAVING THE PROJECT AREA, THE CONTRACTOR SHALL IMPLEMENT ADDITIONAL EROSION PREVENTION AND SEDIMENT CONTROL DEVICES TO LIMIT THE DISCHARGE. DISCHARGES SHALL BE REPORTED TO THE ENGINEER WITHIN 24 HOURS.
- EXCAVATION DEWATERING SHALL BE DISCHARGED TO UPLAND AREAS INTO AN APPROVED EROSION PREVENTION DEVICE, UNLESS WATER IS CLEAR AND FREE OF TURBIDITY. SLOPES STEEPER THAN 2:1 SHALL HAVE STONE ARMORING. SLOPES BETWEEN 2:1 AND 3:1 SHALL HAVE ROLLED EROSION MATTING. SLOPES LESS THAN 3:1 SHALL HAVE SEED AND MULCH.
- WILD APPLE ROAD -DETOUR ROUTE Pomfret CULVERT SITE

SITE DETOUR NOT TO SCALE

СТ

EXISTING LEGEND :

| tel | underground telecom |
|-----|-----------------------------|
| ohw | overhead wires |
| С | utility pole |
| oo | fence/guardrail |
| | sign |
| | trees/vegetation |
| | road right-of-way / tax map |
| | elevation contour |
| | edge of water |
| | ACOE ohw |
| | town easement |
| | |

PROPOSED LEGEND :

454 PROPOSED CONTOUR STONE ARMORING CONCRETE CULVERT/BRIDGE 0 SIGN/TYPE x 452.0' SPOT ELEVATION ACOE INCIDENTAL IMPACT ACOE TEMPORARY IMPACT ACOE PERMANENT IMPACT

ABBREVIATIONS:

| HDPE CONC DI PVC CMP VTRAN | HIGH DENSITY POLYETHYLE CONCRETE DUCTILE IRON POLYVINYL CHLORIDE CORRUGATED METAL PIPE IS VERMONT AGENCY OF TRANSPORTATION |
|---|---|
| MUTCI | D MANUAL ON UN. TRAFFIC CONTROL DEVICES |
| TYP TEMP MIN MAX TBR TBA APPRO EL ROW CTRL NTS N/F | TYPICAL TEMPORARY MINIMUM MAXIMUM TO BE REMOVED TO BE ABANDONED DX APPROXIMATE ELEVATION RIGHT-OF-WAY CONTROL POINT NOT TO SCALE NOW OR FORMERLY |



| | | | STRUCTURE |
|---------------------------------|--|--|---------------------------|
| | WW THIS ANYWA DR | (802) 9 W.EASTENGI W.E | 89-6686 NEERINGPLC.COM |
| | | | |
| | POMFRET | | |
| rox. edge water me of survey | 5218 POMFRET ROAD NORTH POMFRET, VT 05053 (802) 457-3861 | | |
| | PROJECT: | | |
| DR IGWALLS, | WILD APPLE ROAD IMPROVEMENTS | | |
| ACK WITH ABRIC. D 10V:1H | ISSUED FOR: BID & CONSTRUCTION | | |
| | ISSUED DATE: 2023-12-04 | | |
| | PROJ. #: 090-01 | | |
| | REVISIONS | | |
| | # | BY: | DATE: |
| | | | |
| | | | |
| | WILD APPLE ROAD SITE PLAN | | |
| | DRAWING NO: | | |
| | C-1.0 | | |









FEET

STACKED BOULDER WINGWALLS, TYP. OF 4. USE ON-SITE 3-6' (NOM. SIZE) STONES. BACK WITH 1" STONE AND FILTER FABRIC. WALLS TO BE BATTERED 10V:1H

- BOLT POCKET AND GALV BOLT CONNECTIONS. MIN. 2 PER SIDE. FILLED WITH HIGH-STRENGH, NON-SHRINK GROUT

- MEMBRANE - FULL TOP COVERAGE AND DOWN SIDES 2.

CONNECTION. MIN. 2 SHIMS PER SIDE, PER PRECAST PIECE. NOMINAL SPACE FILLED WITH HIGH-STRENGTH, NON-SHRINK GROUT. GROUT

FEET

